

---

**CITY OF KELOWNA**  
**MEMORANDUM**

---

**Date:** May 24, 2018  
**File No.:** Z18-0038  
**To:** Community Planning (KB)  
**From:** Development Engineering Manager (JK)  
**Subject:** 2529 Richter Street RU6 to RM3

---

Development Engineering Department have the following comments and requirements associated with this application. The road and utility upgrading requirements outlined in this report will be a requirement of this development. The Development Engineering Technologist for this project is Jason Angus.

**1. General**

- a. Where there is a possibility of a high water table or surcharging of storm drains during major storm events, non-basement buildings may be required. This must be determined by the engineer and detailed on the Lot Grading Plan required in the drainage section.
- b. Provide easements as may be required.
- c. This proposed subdivision may require the installation of centralized mail delivery equipment. Please contact Rick Ould, Delivery Planning Officer, Canada Post Corporation, 530 Gaston Avenue, Kelowna, BC V1Y 2K0 to obtain further information and to determine suitable location(s) within the development.

**2. Water**

- a. The developer's consulting engineer will determine the domestic and fire protection requirements of this proposed development and establish hydrant requirements and service needs. The bylaw requirement for residential low density multiple housing zone is 150l/s and is available at the site. If it is determined that upgrades to any other existing water distribution system must be made to achieve the required fire flows, additional bonding will be required.
- b. An approved backflow protection device must also be installed on site as required by the City Plumbing Regulation and Water Regulation bylaws.
- c. A water meter is mandatory for this development and must be installed inside a building on the water service inlet as required by the City Plumbing Regulation and Water Regulation bylaws. The developer or building contractor must purchase the meter from the City at the time of application for a building permit from the Inspection Services Department, and prepare the meter setter at his cost

### 3. Sanitary Sewer

- a. The developer's consulting mechanical engineer will determine the development requirements of this proposed development and establish the service needs. Only one service will be permitted for this development. The applicant, at his cost, will arrange for the removal and disconnection of the existing services and the installation of one new larger service.

### 4. Drainage

- a. The developer must engage a consulting civil engineer to provide a storm water management plan for the site, which meets the requirements of the City Storm Water Management Policy and Design Manual. The storm water management plan must also include provision of lot grading plan, minimum basement elevation (MBE), if applicable, and provision of a storm drainage service for the development and / or recommendations for onsite drainage containment and disposal systems.
- b. Provide a detailed Stormwater Management Plan for this development as per the Subdivision, Development and Servicing Bylaw #7900.
- c. There is a possibility of a high water table or surcharging of storm drains during major storm events. This should be considered in the design of the onsite system.

### 5. Roads

- a. Richter street must be upgraded to an 2 lane arterial along the full frontage of this proposed development including curb and gutter, street lights, landscaped boulevard, separated sidewalk, drainage system including catch basins, and pavement removal and replacement up to centerline of Richter street, and re-location or adjustment of utility appurtenances if required to accommodate the upgrading construction. Road cross section to be used is a modified SS-R5 which can be supplied at detail design.
- b. Morrison Ave must be upgraded to an 2 lane collector along the full frontage of this proposed development including curb and gutter, street lights, landscaped boulevard, separated sidewalk, drainage system including catch basins, and pavement removal and replacement up to centerline of Richter street, and re-location or adjustment of utility appurtenances if required to accommodate the upgrading construction. Road cross section to be used is a modified SS-R5 which can be supplied at detail design.
- c. The laneway must be upgraded to a paved standard complete with a concrete driveway let down exiting onto Morrison Ave. Standards SS-R2 and SS-C7 are to be used in detail design.

### 6. Road Dedication and Subdivsion Requirements

- a. Grant Statutory Rights of Way if required for utility services.
- b. If any road dedication affects lands encumbered by a Utility right-of-way (such as BC Hydro Gas, etc.) please obtain the approval of the utility prior to application for final subdivision approval. Any works required by the utility as a consequence of the road dedication must be incorporated in the construction drawings submitted to the City's Development Manager
- c. Vehicle access for the development must be from the north/south laneway.

- d. Provide 6m corner rounding at intersection of Richter Street and Morrison Ave.
- e. Provide curb extensions on Morrison Ave at the intersection of Morrison and Richter St.

## **7. Power and Telecommunication Services and Street Lights**

- a. All proposed distribution and service connections are to be installed underground. Existing distribution and service connections, on that portion of a road immediately adjacent to the site, are to be relocated and installed underground.
- b. Streetlights must be installed on all roads.
- c. Make servicing applications to the respective Power and Telecommunication utility companies. The utility companies are required to obtain the City's approval before commencing construction.
- d. Remove existing poles and utilities, where necessary. Remove aerial trespass (es).

## **8. Design and Construction**

- a. Design, construction supervision and inspection of all off-site civil works and site servicing must be performed by a Consulting Civil Engineer and all such work is subject to the approval of the City Engineer. Drawings must conform to City standards and requirements.
- b. Engineering drawing submissions are to be in accordance with the City's "Engineering Drawing Submission Requirements" Policy. Please note the number of sets and drawings required for submissions.
- c. Quality Control and Assurance Plans must be provided in accordance with the Subdivision, Development & Servicing Bylaw No. 7900 (refer to Part 5 and Schedule 3).
- d. A "Consulting Engineering Confirmation Letter" (City document 'C') must be completed prior to submission of any designs.
- e. Before any construction related to the requirements of this subdivision application commences, design drawings prepared by a professional engineer must be submitted to the City's Development Engineering Department. The design drawings must first be "Issued for Construction" by the City Engineer. On examination of design drawings, it may be determined that rights-of-way are required for current or future needs.

## **9. Servicing Agreements for Works and Services**

- a. A Servicing Agreement is required for all works and services on City lands in accordance with the Subdivision, Development & Servicing Bylaw No. 7900. The applicant's Engineer, prior to preparation of Servicing Agreements, must provide adequate drawings and estimates for the required works. The Servicing Agreement must be in the form as described in Schedule 2 of the bylaw.
- b. Part 3, "Security for Works and Services", of the Bylaw, describes the Bonding and Insurance requirements of the Owner. The liability limit is not to be less than

\$5,000,000 and the City is to be named on the insurance policy as an additional insured

#### 10. Geotechnical Study.

- a. Provide a geotechnical report prepared by a Professional Engineer competent in the field of hydro-geotechnical engineering to address the items below: **NOTE: The City is relying on the Geotechnical Engineer's report to prevent any damage to property and/or injury to persons from occurring as a result of problems with soil slippage or soil instability related to this proposed subdivision.**
- i. The Geotechnical report must be submitted prior to submission of Engineering drawings or application for subdivision approval.
  - ii. Area ground water characteristics, including any springs and overland surface drainage courses traversing the property. Identify any monitoring required.
  - iii. Site suitability for development.
  - iv. Site soil characteristics (i.e. fill areas, sulphate content, unsuitable soils such as organic material, etc.).
  - v. Any special requirements for construction of roads, utilities and building structures.
  - vi. Recommendations for items that should be included in a Restrictive Covenant.
  - vii. Recommendations for roof drains, perimeter drains and septic tank effluent on the site.
  - viii. Any items required in other sections of this document.
  - ix. Additional geotechnical survey may be necessary for building foundations, etc

#### 11. Charges and Fees

- a. Development Cost Charges (DCC's) are payable
- b. Fees per the "Development Application Fees Bylaw" include:
  - i. Street/Traffic Sign Fees: at cost if required (to be determined after design).
  - ii. Survey Monument, Replacement Fee: \$1,200.00 (GST exempt) – only if disturbed.
- c. Engineering and Inspection Fee: 3.5% of construction value (plus GST)

  
James Kay, P.Eng.

Development Engineering Manager

JA

# SCHEDULE

**A**

This forms part of application



# **Z18-0056**

Planner  
Initials

KB

City of  
**Kelowna**  
COMMUNITY PLANNING





ALL CONTRACTORS ARE REQUIRED TO PERFORM THEIR WORK AND SUPPLY THEIR PRODUCTS IN COMPLIANCE WITH ALL BUILDING CODES AND LAWS OF THE PROVINCE OF BRITISH COLUMBIA

This drawing is an instrument of service and the property of New Town Services. The use of this drawing shall be restricted to the original site for which it was prepared and publication thereof is expressly limited to such use.

This drawing must not be scaled

Verify all dimensions and datums prior to commencement of work.

Report all errors and omissions to the Architect.



Seal

Revision		
No	Date	Description
1	18-05-10	ISSUED FOR DP
2	18-06-21	RE-ISSUED FOR DP

1 RICHTER SITE PLAN  
A4.01 1 : 75

SCHEDULE

B

This forms part of application  
# Z18-0056

Planner Initials

KB

City of Kelowna

COMMUNITY PLANNING

project title  
RICHTER TOWNHOUSES

project address  
2529 RICHTER STREET,  
KELOWNA, BC

project no. 4055

file no.

drawing title  
SITE PLAN

designed L.A. scale 1 : 75

drawn L.A.

checked K.F.

drawing no.

A2.00

plotted 7/20/2018 9:25:29 AM

NOT FOR CONSTRUCTION