# **CITY OF KELOWNA**

# **MEMORANDUM**

Date:

June 28, 2018

File No.:

Z18-0066

To:

Community Planning (TA)

From:

Development Engineering Manager (JK)

Subject:

365 367 Hein Rd

RU6 to RM5

The Development Engineering Department has the following comments and requirements and are subject to review and requirements from the Ministry of Transportation (MOTI). The road and utility upgrading requirements outlined in this report will be a requirement of this development. The Development Engineering Technologist for this project is Andy Marshall

#### 1. Domestic Water and Fire Protection

The property is located within the Black Mountain Irrigation District (BMID) service area. The water system must be capable of supplying domestic and fire flow demands of the project in accordance with the Subdivision, Development & Servicing Bylaw. The developer is responsible, if necessary, to arrange with BMID staff for any service improvements and, if necessary, the decommissioning of existing services. Only one water service permitted.

## 2. Sanitary Sewer

- (a) Our records indicate that this property is currently serviced with a 100mm-diameter sanitary sewer service. The applicant's consulting mechanical engineer will determine the requirements of the proposed development and establish the service needs. Only one service will be permitted for this development. If required, the applicant will arrange for the removal and disconnection of the existing service and the installation of one new larger service at the applicants cost. An inspection chamber and brooks box are required on the service.
- (b) 365 375 Hein Rd is within Sanitary Sewer Spec Area 22C. The developer will be required to cash commute, pay in full, the specified area charge outstanding for this property = \$1426.61.
- (c) The specified area charges for this development are calculated as: (24 units x 0.7 SFE (Single family equivalent)) 1SFE (credit for original property) X \$1426.61 = \$22,540.44

#### 3. Storm Drainage

a) The developer must engage a consulting civil engineer to provide a storm water management plan for this site which meets the requirements of the City Subdivision Development and Servicing Bylaw 7900. The storm water management plan must also include provision of lot grading plans, minimum basement elevations (MBE), if applicable, and provision of a storm drainage service and recommendations for onsite drainage containment and disposal systems b) The developer must engage a consulting civil engineer to provide a storm water design for Hein Rd for this development which meets the requirements of the City Subdivision Development and Servicing Bylaw 7900.

### 4. Road Improvements

(a) Hein Rd must be upgraded to an urban standard along the full frontage of this proposed development, including irrigated and landscape boulevard. For Reference use road cross section SS-R5

## 5. Road Dedication and Subdivision Requirements

- (a) Grant Statutory Rights of Way if required for utility services.
- (b) If any road dedication or closure affects lands encumbered by a Utility right-of-way (such as Hydro, TELUS, Gas, etc.) please obtain the approval of the utility. Any works required by the utility as a consequence of the road dedication or closure must be incorporated in the construction drawings submitted to the City's Development Manager

#### 6. Electric Power and Telecommunication Services

The electrical and telecommunication services to this building must be installed in an underground duct system, and the building must be connected by an underground service. It is the developer's responsibility to make a servicing application with the respective electric power, telephone and cable transmission companies to arrange for these services, which would be at the applicant's cost.

#### 7. Design and Construction

- (d) Design, construction supervision and inspection of all off-site civil works and site servicing must be performed by a Consulting Civil Engineer and all such work is subject to the approval of the City Engineer. Drawings must conform to City standards and requirements.
- (e) Engineering drawing submissions are to be in accordance with the City's "Engineering Drawing Submission Requirements" Policy. Please note the number of sets and drawings required for submissions.
- (f) Quality Control and Assurance Plans must be provided in accordance with the Subdivision, Development & Servicing Bylaw No. 7900 (refer to Part 5 and Schedule 3).
- (g) A "Consulting Engineering Confirmation Letter" (City document 'C') must be completed prior to submission of any designs.
- (h) Before any construction related to the requirements of this subdivision application commences, design drawings prepared by a professional engineer must be submitted to the City's Works & Utilities Department. The design drawings must first be "Issued for Construction" by the City Engineer. On examination of design drawings, it may be determined that rights-of-way are required for current or future needs.

#### 8. Other Engineering comments

(a) Underground parking entrance grade and radius to be confirmed.

# 9. <u>Geotechnical Report</u>

As a requirement of this application the owner must provide a geotechnical report prepared by a Professional Engineer qualified in the field of hydro-geotechnical survey to address the following:

- (a) Area ground water characteristics.
- (b) Site suitability for development, unstable soils, etc.
- (c) Drill and / or excavate test holes on the site and install pisometers if necessary. Log test hole data to identify soil characteristics, identify areas of fill if any. Identify unacceptable fill material, analyse soil sulphate content, identify unsuitable underlying soils such as peat, etc. and make recommendations for remediation if necessary.
- (d) List extraordinary requirements that may be required to accommodate construction of roads and underground utilities as well as building foundation designs.
- (e) Additional geotechnical survey may be necessary for building foundations, etc.

# 10. Servicing Agreement for Works and Services

- (a) A Servicing Agreement is required for all works and services on City lands in accordance with the Subdivision, Development & Servicing Bylaw No. 7900. The applicant's Engineer, prior to preparation of Servicing Agreements, must provide adequate drawings and estimates for the required works. The Servicing Agreement must be in the form as described in Schedule 2 of the bylaw.
- (b) Part 3, "Security for Works and Services", of the Bylaw, describes the Bonding and Insurance requirements of the Owner. The liability limit is not to be less than \$5,000,000 and the City is to be named on the insurance policy as an additional insured.

#### 11. Administration Charge

An administration charge will be assessed for processing of this application, review and approval of engineering designs and construction inspection. The administration charge is calculated as (3.5% of Total Off-Site Construction Cost plus GST).


#### 12. Survey, Monument and Iron Pins

If any legal survey monuments or property iron pins are removed or disturbed during construction, the developer will be invoiced a flat sum of \$1,200.00 per incident to cover the cost of replacement and legal registration. Security bonding will not be released until restitution is made.

James Kay, P. Eng.

Development Engineering Manager

agm





All figures have been based on preliminary information and are subject to verification. The material contained herein is indicative only and may be subject to approval by the responsible authorities(s), or other factors beyond the control of New Town; receiving parties should not use this material to form the basis of any financial feasibility, contractual negotiation or sale documents

# **PRELIMINARY**



Copyright

© 2018 Notes

Notes

This drawing must be read in conjunction with all other drawings specifications, schedules and consultant documents. Any discrepancies must be reported to New Town Services. If in any doubt whatsoever contact

New Town Services.





Project
HEIN ROAD APARTMENTS

385 & 387 HEN ROAD
KELOWNA, BC, VIX 4A2
Client

KELOWNA, BC, V1X 4A2
Client
DARSHAN PANNU

300 TERAI COURT
KELOWNA, BC, V1X 5V6

Drawing title SITE PLAN

Date created Checked 07/02/18 NTAE Scale 1: 400 @ 11x17

A 1464 St Paul Street Kelowna BC V1Y 2E6 E office@newtownservices.net T 1 250 860 8185

Project number Drawing number Revision 4017 SD003 C Status PRELIMINARY