

---

# CITY OF KELOWNA

## MEMORANDUM

**Date:** August 27, 2021  
**File No.:** Z21-0076  
**To:** Planning and Development Officer (MT)  
**From:** Development Engineering Manager (RO)  
**Subject:** 2117 Kaslo Ct.

**SCHEDULE** A

This forms part of application  
# Z21-0076

Planner  
Initials MT



RU1 to RU6

---

The Development Engineering Branch has the following comments and requirements associated with this rezoning application to rezone the subject property from RU1 – Large Lot Housing zone to RU6 – Two Dwelling House zone. The Development Engineering Technician for this project is Aaron Sangster.

**1. General**


- a) The following requirements are valid for one (1) years from the reference date of this memo, or until the application has been closed, whichever occurs first. The City of Kelowna reserves the rights to update/change some or all items in this memo once these time limits have been reached.

**2. Road Improvements**

- a) Kaslo Ct. must be upgraded to an urban standard along the full frontage of this proposed development sidewalk, letdown, irrigated landscaped boulevard, drainage system including catch basins, manholes and pavement removal and replacement and re-location or adjustment of utility appurtenances if required to accommodate the upgrading construction. Cash-in-lieu instead of immediate construction is required, and the City will initiate the work later, on its own construction schedule. The cash-in-lieu amount is determined to be **\$30,422.10** not including utility service cost.
- b) Development Engineering Fee (3.5% of estimated construction cost) = **\$1,028.57** (\$979.59 + \$48.98 GST)

**3. Domestic Water and Fire Protection**

- a) This property is currently serviced with 19mm-diameter water service. The developer's consulting mechanical engineer will determine the domestic, fire protection requirements of this proposed development and establish hydrant requirements and service needs. Service upgrades can be provided by the City at the applicant's cost (if required). One service per lot only.
- b) The developer's consulting mechanical engineer will determine the domestic, fire protection requirements of this proposed development and establish hydrant requirements and service needs.

<b>SCHEDULE</b>		<b>A</b>
This forms part of application		
# Z21-0076		
Planner Initials	MT	 <b>City of Kelowna</b> <small>DEVELOPMENT PLANNING</small>

#### 4. **Sanitary Sewer**

- a) This property is currently serviced with one 100 mm sanitary service. The developer's consulting mechanical engineer will determine the development requirements of this proposed development and establish the service needs. Only one service will be permitted for each legal lot. The applicant, at their cost, will arrange for the removal and disconnection of the existing services and installation of one new larger service, if necessary. An inspection chamber is required to be installed as per SS-S7.

#### 5. **Storm Drainage**

- a) The property is located within the City of Kelowna drainage service area. For on-site disposal of drainage water, a hydrogeotechnical report will be required complete with a design for the disposal method (i.e. trench drain / rock pit). The Lot Grading Plan must show the design and location of these systems.
- b) Provide the following drawings:
  - i. A detailed Lot Grading Plan (indicate on the Lot Grading Plan any slopes that are steeper than 30% and areas that have greater than 1.0 m of fill);
  - ii. A detailed Stormwater Management Plan for this subdivision; and,
  - iii. An Erosion and Sediment Control Plan is to be prepared by a Professional Engineer proficient in the field of erosion and sediment control. The plan is to be prepared as per section 3.14 of Schedule 4 of Bylaw 7900. If a line item for ESC is not included in the Engineer's cost estimate for off-site work, then an additional 3% will be added to the performance security based on the total off-site construction estimate.
- c) On-site detention systems are to be compliant with Bylaw 7900, Schedule 4, Section 3.11.1 *Detention Storage*.
- d) As per Bylaw 7900, Schedule 4, Section 3.1.3 *Climate Change*, the capacity of storm works will include an additional 15 percent (15%) upward adjustment, and applied to the rainfall intensity curve stage (IDF) in Section 3.7.2.
- e) Show details of dedications, rights-of-way, setbacks and non-disturbance areas on the lot Grading Plan.
- f) Register right of ways on private properties for all the storm water infrastructure carrying, conveying, detaining and/or retaining storm water that is generated from the public properties, public road right of ways, and golf course lands.
- g) Where structures are designed or constructed below the proven high groundwater table, permanent groundwater pumping will not be permitted to discharge to the storm system. The City will approve designs that include provisions for eliminating groundwater penetration into the structure, while addressing buoyancy concerns. These design aspects must be reviewed and approved by the City Engineer.

#### 6. **Electric Power and Telecommunication Services**

- a) It is the developer's responsibility to make a servicing application with the respective electric power, telephone and cable transmission companies to arrange for these services, which would be at the applicant's cost.
- b) If any road dedication or closure affects lands encumbered by a Utility right-of-way (such as Hydro, Telus, Gas, etc.) please obtain the approval of the utility. Any works required by

the utility as a consequence of the road dedication or closure must be incorporated in the construction drawings submitted to the City's Development Manager.

## 7. Road Dedication and Subdivision Requirements


- a) Provide all necessary Statutory Rights-of-Way for any utility corridors as required.
- b) If any road dedication affects lands encumbered by a Utility right-of-way (such as Fortis, etc.) please obtain the approval of the utility prior to application for final subdivision approval. Any works required by the utility as a consequence of the road dedication must be incorporated in the construction drawings submitted to the City's Development Manager.
- c) Existing driveway must be reduced to 6.0m to meet bylaws 7900.

## 8. Geotechnical Report

- a) Provide a comprehensive geotechnical report (3 copies), prepared by a Professional Engineer competent in the field of hydro-geotechnical engineering to address the items below: **NOTE: The City is relying on the Geotechnical Engineer's report to prevent any damage to property and/or injury to persons from occurring as a result of problems with soil slippage or soil instability related to this proposed subdivision.**

The Geotechnical reports must be submitted to the Planning and Development Services Department (Planning & Development Officer) for distribution to the Works & Utilities Department and Inspection Services Division prior to submission of Engineering drawings or application for subdivision approval.

- (i) Area ground water characteristics, including any springs and overland surface drainage courses traversing the property. Identify any monitoring required.
- (ii) Site suitability for development.
- (iii) Site soil characteristics (i.e. fill areas, sulphate content, unsuitable soils such as organic material, etc.).
- (iv) Any special requirements for construction of roads, utilities and building structures.
- (v) Site suitability for development.
- (vi) Suitability of on-site disposal of storm water and sanitary waste, including effects upon adjoining lands.
- ii) Site soil characteristics (i.e. fill areas, sulphate content, unsuitable soils such as organic material, etc.).
- iii) Recommendations for items that should be included in a Restrictive Covenant.
- iv) Any special requirements for construction of roads, utilities, and building structures.
- v) Any items required in other sections of this document.

<b>SCHEDULE</b>		<b>A</b>
This forms part of application		
# Z21-0076		
Planner Initials	MT	 <b>City of Kelowna</b> DEVELOPMENT PLANNING

- vi) Recommendations for erosion and sedimentation controls for water and wind.
- vii) Recommendations for roof drains and perimeter drains.
- viii) Any items required in other sections of this document.

## 9. **Charges and Fees**

- a) Development Cost Charges (DCC's) are payable.
- b) Fees per the "Development Application Fees Bylaw" include:
  - i) Survey Monument, Replacement Fee: \$1,200.00 (GST exempt) – only if disturbed.
  - ii) Engineering and Inspection Fee: 3.5% of construction value (plus GST).

---

Ryan O'Sullivan  
Development Engineering Manager

AS

<b>SCHEDULE</b>		<b>A</b>
This forms part of application		
# Z21-0076		
Planner Initials	MT	 City of <b>Kelowna</b> DEVELOPMENT PLANNING




FRONT ELEVATION



LEFT ELEVATION



REAR ELEVATION



RIGHT ELEVATION

REVISION TABLE		REVISION BY	DESCRIPTION
NUMBER	DATE		

**PROPOSED DUPLEX**  
2117 KASLO COURT KELOWNA

DATE:

2021-09-18

SCALE:

1/4" = 1'-0"

SHEET:

1



**ATTACHMENT**
A

This forms part of application  
# Z21-0076

Planner  
Initials
MT

City of  
**Kelowna**  
DEVELOPMENT PLANNING



REVISION TABLE	
NUMBER	DATE

PROPOSED DUPLEX  
2117 KASLO COURT KELOWNA




## A

# Z21-0076



MT



Upper Setback 2.31m  
Main Floor Setback 2.06m



REVISER BY	
------------	--

3





2117 Kaslo Court Kelowna BC  
Lot 26 KAP 25943 Sec 26 Township 26

Lot Area 846m<sup>2</sup>  
Site Coverage 221.58m<sup>2</sup> = 26.19 %  
Driveways 99.81m Total coverage 38.0%

REVISION TABLE		DESCRIPTION
NUMBER	DATE	REVISOR


PROPOSED DUPLEX  
2117 KASLO COURT KELOWNA

DATE:  
2021-09-18

SCALE:  
1/4" = 1'-0"

SHEET:





ATTACHMENT

A

This forms part of application


# Z21-0076

Planner Initials

MT



City of Kelowna

DEVELOPMENT PLANNING



2117 Kaslo Court Kelowna BC  
Lot 26 KAP 25943 Sec 26 Township 26

Lot Area 846m<sup>2</sup>  
Site Coverage 221.58m<sup>2</sup> = 26.19 %  
Driveways 99.81m Total coverage 38.0%



REVISION TABLE		DESCRIPTION
NUMBER	DATE	REVISION BY

PROPOSED DUPLEX  
2117 KASLO COURT KELOWNA

DATE:  
2021-09-18

SCALE:  
1/4" = 1'-0"

SHEET: